

GENERAL NOTES

THESE INSTALLATION INSTRUCTIONS ARE A SUPPLEMENT TO THE APPROVED SHOP DRAWINGS. USE IN CONJUNCTION WITH THOSE DRAWINGS.

HANDLING, STORING AND PROTECTING ALUMINUM MATERIAL

THE FOLLOWING PRECAUTIONS ARE RECOMMENDED TO ASSURE EARLY ACCEPTANCE OF YOUR PRODUCTS AND WORKMANSHIP.

- A) HANDLE CAREFULLY - DO NOT DROP FROM THE TRUCK. STACK WITH ADEQUATE SEPARATION SO MATERIAL WILL NOT RUB TOGETHER. STORE OFF THE GROUND. PROTECT AGAINST ELEMENTS AND OTHER CONSTRUCTION TRADES.
- B) KEEP MATERIAL AWAY FROM WATER, MUD AND SPRAY - PREVENT CEMENT, PLASTER AND OTHER MATERIALS FROM DAMAGING THE FINISH.
- C) PROTECT THE MATERIALS AFTER ERECTION, BY WRAPPING WITH KRAFT PAPER - OR BY ERECTING VISQUEEN/CANVAS SPLATTER SCREENS. CEMENT, PLASTER, TERRAZZO AND OTHER ALKALINE MATERIALS ARE VERY HARMFUL TO THE FINISH AND SHOULD BE REMOVED WITH WATER AND MILD SOAP BEFORE SETTING OCCURS. UNDER NO CIRCUMSTANCES ALLOW THESE MATERIALS TO TO DRY OR PERMANENT STAINING WILL OCCUR.

GENERAL RULES

THE FOLLOWING PRACTICES ARE RECOMMENDED FOR ALL WALL INSTALLATIONS.

- A) READ COMPLETE INSTRUCTIONS BEFORE ORDERING GLASS OR FABRICATING MATERIAL.
- B) CHECK SHOP DRAWINGS TO BECOME THOROUGHLY FAMILIAR WITH THE JOB.
- C) ALL MATERIALS ARE TO BE INSTALLED PLUMB, LEVEL AND TRUE.
- D) ALL WORK SHOULD START FROM ESTABLISHED BENCH MARKS AND COLUMN CENTER LINES ESTABLISHED BY THE ARCHITECTURAL DRAWINGS AND THE GENERAL CONTRACTOR.
- E) THE SEQUENCE OF ERECTION SHOULD BE COORDINATED WITH THE JOB SUPERINTENDENT SO DELAYS ARE PREVENTED AND RISK OF MATERIAL DAMAGE IS MINIMIZED. IF PRESETTING OF ANCHORAGE IS REQUIRED, COORDINATE WITH GENERAL CONTRACTOR AND SUPERVISE LOCATION.
- F) MAKE CERTAIN CONSTRUCTION WHICH WILL RECEIVE YOUR MATERIALS IS ACCORDING TO THE CONTRACT DOCUMENTS. IF NOT, NOTIFY THE GENERAL CONTRACTOR IN WRITING AND RESOLVE DIFFERENCES BEFORE PROCEEDING WITH YOUR WORK.

- G) INSULATE ALL ALUMINUM TO BE PLACED DIRECTLY IN CONTACT WITH THE MASONRY OR INCOMPATIBLE MATERIALS WITH A HEAVY COAT OF ZINC CHROMATE OR BITUMINOUS PAINT.
- H) FOLLOW KAWNEER INSTALLATION AND GLAZING INSTRUCTIONS.
- J) CHECK ALL MATERIAL ON ARRIVAL FOR QUANTITY.
- K) BE SURE TO HAVE ALL THE MATERIALS AND TOOLS NEEDED TO BEGIN THE INSTALLATION.
 - 1. APPROVED SHOP DRAWINGS.
 - 2. LEVEL AND PLUMB (TRANSIT).
 - 3. FASTENERS AND REQUIRED DRIVERS.
 - 4. PERIMETERS AND ACCESSORIES SUCH AS ANCHORS, FASTENERS, SLEEVES AND/OR SPLICE CAPS.
 - 5. SEALING MATERIALS.
 - 6. GLAZING MATERIALS.
- L) FOLLOW SEALANT MANUFACTURER'S RECOMMENDATIONS FOR PROPER SEALANT AND APPLICATION. ALL SEALANTS AND MASTICS MUST BE COMPATIBLE WITH ALL SURFACES INCLUDING OTHER SEALANT SURFACES. WHERE REQUIRED ALL SEALANTS MUST ADHERE TO ALL SURFACES INCLUDING OTHER SEALANT SURFACES.

1600 SYSTEM™1 NOTES

1600 SYSTEM™1 IS AVAILABLE WITH 1" FRAMING MEMBERS WHICH ACCEPT BOTH 1" AND 1/4" INFILLS. ALSO 1/4" FRAMING MEMBERS WHICH ACCEPT 1/4" INFILLS ONLY ARE AVAILABLE.

GLASS BITE IS 1/2" AT VERTICALS AND HORIZONTALS. GLASS SIZES MUST BE CALCULATED FROM APPROVED SHOP DRAWINGS.

UNLESS OTHERWISE SPECIFIED, IT IS RECOMMENDED THAT SILICONE SEALANT BE USED FOR ALL INTERNAL SEALS.

SEALANT MUST BE APPLIED PER THE SEALANT MANUFACTURER'S RECOMMENDATIONS AND PASS ALL ADHESION AND COMPATIBILITY TESTING. AT ALL JOINT SEALS, SEALANT MUST ADHERE TO METAL, GASKETS, THERMAL SEPARATOR AND JOINT PLUG MATERIALS. CLEAN ALL SURFACES PRIOR TO APPLICATION OF SEALANT AND PRIME WHERE NECESSARY TO ACHIEVE PROPER ADHESION.


SHIM ALL SILL HORIZONTALS AT SETTING BLOCK LOCATIONS.

OPEN BACK HORIZONTAL NOTES


THE OPEN BACK HORIZONTAL IS TO BE TYPICALLY USED FOR ALL HEAD/SILL AND LAST BAY INTERMEDIATE HORIZONTALS.

THE OPEN BACK HORIZONTAL CAN BE USED AT OTHER CONDITIONS IF IT IS AN ADVANTAGE TO THE JOB DESIGN.

THE SHEAR BLOCK AT ALL OPEN BACK INTERMEDIATE HORIZONTALS HAS THE OPTION TO BE PRE-INSTALLED INTO THE HORIZONTAL BEFORE HORIZONTALS ARE INSTALLED



WHEN THE OPEN SIDE OF THE OPEN BACK HORIZONTAL IS EXPOSED AND AT EYE LEVEL A SNAP-IN FILLER IS AVAILABLE.



WHEN THE SNAP-IN FILLER IS NOT USED, AND DUE TO STANDARD COMMERCIAL EXTRUDING TOLERANCES, IT MAY BE REQUIRED TO USE A 4" PIECE OF THE FILLER AT EACH END OF A HORIZONTAL.

USE PART 162316 FOR THE 6" DEEP SYSTEM
USE PART 162317 FOR THE 7 1/2" DEEP SYSTEM


OPEN BACK HORIZONTALS AT 90° AND 135° CORNERS

WHENEVER POSSIBLE AVOID USING OPEN BACK HORIZONTALS AT 90° AND 135° CORNERS. IF USING THE OPEN BACK HORIZONTAL BECOMES ABSOLUTELY NECESSARY THE SHEAR BLOCK CONNECTION WILL BE AS SHOWN BELOW.


ALSO REFER TO CORNER INSTRUCTIONS 162972

CONFIDENTIAL AND PROPRIETARY INFORMATION KAWNEER COMPANY INC.

THESE DRAWINGS ARE THE SOLE AND EXCLUSIVE PROPERTY OF KAWNEER AND CONTAIN SENSITIVE, PRIVILEGED OR CONFIDENTIAL INFORMATION WHICH MAY BE USED ONLY FOR ITS BENEFIT. THE DISCLOSURE OF THESE DRAWINGS TO UNAUTHORIZED PERSONS IS STRICTLY PROHIBITED. THIS DOCUMENT AND ALL COPIES MUST BE RETURNED UPON DEMAND.
© COPYRIGHT KAWNEER COMPANY, INC., 2013



THE OPEN SIDE OF THE OPEN BACK HORIZONTAL IS TO BE POSITIONED AS SHOWN BELOW. THE INTERMEDIATE HORIZONTAL IS POSITIONED OPEN SIDE DOWN FOR DEAD LOAD SUPPORT.



Product Engineering & Development

95449-115
04/21/17

STEP 1 - CHECK OPENINGS


ELEVATIONS AND SLABS MUST BE WITHIN ADJUSTMENT OF ANCHORING SYSTEM. SEE APPROVED SHOP DRAWINGS FOR ALLOWABLE ADJUSTMENT.

ANCHORING SURFACES OF PERIMETER CONSTRUCTION MUST BE LEVEL AND PLUMB WITHIN THE ADJUSTMENT LIMITS OF THE HEAD, SILL AND JAMB. SEE APPROVED SHOP DRAWINGS FOR ALLOWABLE ADJUSTMENT.

STEP 2 - LAY OUT ANCHOR AND MULLION CENTERLINES

USE WALL LINES ESTABLISHED BY THE GENERAL CONTRACTOR. ON EACH FLOOR LAY OUT A REFERENCE LINE TO ESTABLISH IN AND OUT WALL LOCATIONS.

USE COLUMN CENTER LINES ESTABLISHED BY THE GENERAL CONTRACTOR. ON EACH FLOOR LAY OUT MULLION CENTER LINES AND ANCHOR CENTER LINES.



STEP 3 - INSTALL PRESET ANCHORS IF APPLICABLE

USING LOCATION LINES PREVIOUSLY ESTABLISHED INSTALL PRESET ANCHORS IN PLACE PER APPROVED SHOP DRAWINGS.


STEP 4 - FRAME ASSEMBLY

ATTACH ANCHORS TO MULLIONS WHERE APPLICABLE.

ANCHOR PREP MAY BE FABRICATED IN THE FIELD OR FACTORY. CONSULT APPROVED SHOP DRAWINGS FOR CORRECT METHOD.


STANDARD ANCHOR PREP IS THRU-BOLTED AT INTERMEDIATE VERTICALS AND TAPPING PLATES ARE USED AT JAMB VERTICALS. REFER TO APPROVED SHOP DRAWINGS FOR CORRECT METHOD.

WHEN WELDING ANCHORS, PROTECT INSTALLED GLASS AND METAL FROM WELD SPLATTER.




DO NOT OVER TIGHTEN ANCHOR CONNECTIONS. TIGHTEN TO A "SNUG TIGHT" POSITION WITH PARTS BROUGHT INTO GOOD CONTACT. BE SURE ANY SPRING TYPE LOCK WASHERS ARE COMPRESSED. THEN TIGHTEN APPROXIMATELY 1/2 MORE TURN.

ATTACH SHEAR BLOCKS.



TYPICAL INTERMEDIATE SHEAR BLOCKS
162377 (6" SYSTEM)
162378 (7-1/2" SYSTEM)




HEAD AND SILL SHEAR BLOCKS
162331 (6" SYSTEM)
162332 (7-1/2" SYSTEM)

REFERENCE INSTRUCTIONS 162983 FOR EXTERIOR FRAME PERIMETERS HEAD AND SILL SHEAR BLOCKS
162384 (6" SYSTEM)
162385 (7-1/2" SYSTEM)

STEP 4 - FRAME ASSEMBLY


ATTACH SHEAR BLOCKS



HEAD/SILL SHEAR BLOCK/ANCHOR WHERE APPLICABLE AND SHOWN BELOW.

162314 (6" SYSTEM AT JAMBS)
162315 (7-1/2" SYSTEM AT JAMBS)
162342 (6" SYSTEM AT MULLIONS)
162343 (7-1/2" SYSTEM AT MULLIONS)

STRUCTURAL INTEGRITY OF ANCHOR AND FASTENERS MUST BE CHECKED BY FACTORY ENGINEERS.



ANCHOR FASTENER LOCATIONS PER APPROVED SHOP DRAWINGS

SHEAR BLOCK/ANCHOR

128396 SCREWS
#12 x 7/16"
PAN HEAD TYPE B


STEP 5 - INSTALL THERMAL BREAK



162310

DO NOT STRETCH WHEN REMOVING FROM COIL AND CARTON

DO NOT STRETCH DURING INSTALLATION



162310
THERMAL BREAK

STEP 5 - INSTALL THERMAL BREAK

162310
THERMAL BREAK




OPTION TO INSTALL THERMAL BREAK AFTER VERTICALS AND HORIZONTALS ARE INSTALLED

THERMAL BREAK TO BE SAME LENGTH AS VERTICAL MULLIONS

THERMAL BREAK TO BE 1/4" SHORT AT EACH END OF HORIZONTALS

1/4"

INSTALL HEAD AND SILL END CAPS
162388 (1" FRAMING)
162389 (1/4" FRAMING)
SET IN SEALANT



NOT REQUIRED AT EXTERIOR FRAME PERIMETERS SHOWN IN INSTRUCTIONS 162983 AND AT OPTIONAL PERIMETER FILLERS 162022 AND 162023




1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS

Product Engineering & Development

95449-115
04/21/17

STEP 6 - PERIMETERS WHERE APPLICABLE


INSTALL PERIMETER MEMBERS PER APPROVED SHOP DRAWINGS. PERIMETER MEMBERS CAN OCCUR AT HEAD, SILL OR JAMB CONDITIONS.



STEP 7 - INSTALL VERTICAL MULLIONS

DIMENSION BUILD-UP CHECK CHECK

OVERALL FRAME DIMENSIONS ABOUT EVERY FIVE MULLIONS ON LONG RUNS. THIS IS TO AVOID DIMENSION BUILD-UP



STEP 7 - INSTALL VERTICAL MULLIONS


"F" OR "T" ANCHORS WHERE APPLICABLE

REFERENCE INSTRUCTIONS 162983 FOR EXTERIOR FRAME PERIMETERS

THESE SHEAR BLOCKS MAY NEED TO BE REMOVED TO INSTALL A ANCHOR FASTENER THAT MIGHT BE LOCATED CLOSE TO THE MULLION

"F" AND "T" ANCHOR FASTENER LOCATIONS PER APPROVED SHOP DRAWINGS

AT MULLION JAMB SIDE, APPLY (2) 128396 SCREWS AS SHOWN TO CENTER F-CLIPS AS REQUIRED.




"F" AND "T" ANCHOR FASTENER LOCATIONS PER APPROVED SHOP DRAWINGS

STEP 7 - INSTALL VERTICAL MULLIONS

HEAD/SILL SHEAR BLOCK/ANCHOR WHERE APPLICABLE.

CAN NOT BE USED WITH EXTERIOR FRAME PERIMETERS SHOWN ON INSTRUCTIONS 162983

162314 (6" SYSTEM AT JAMBS)
162315 (7-1/2" SYSTEM AT JAMBS)
162342 (6" SYSTEM AT MULLIONS)
162343 (7-1/2" SYSTEM AT MULLIONS)



STRUCTURAL SHIMMING IS REQUIRED AT SILL TO ACCOMPLISH DESIGNED PERIMETER SEAL WIDTH

ANCHOR FASTENER LOCATIONS PER APPROVED SHOP DRAWINGS

ANCHOR FASTENER LOCATIONS PER APPROVED SHOP DRAWINGS

162970 SHEET 03 OF 09

STEP 7 - INSTALL VERTICAL MULLIONS

VERTICAL SPLICE JOINTS WHERE APPLICABLE.

SLEEVE IS FACTORY TAPED INTO THE BOTTOM OF THE TOP VERTICAL

REMOVE THE TAPE AND LET THE SLEEVE SLIDE DOWN TO THE FACTORY APPLIED STOP SCREW

FIELD APPLIED FIXING SCREW 128348 #10 x 1-1/4" FLAT HEAD SELF DRILLING

SHOP APPLIED STOP SCREW 128267 #12 x 1" PAN HEAD TYPE AB

USE TEMPORARY SPACERS FOR JOINT DIMENSION

SPLICE JOINT WHEN IT OCCURS AT A HORIZONTAL

KAWNEER
AN ARCONIC COMPANY

Product Engineering & Development

95449-115
04/21/17


1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS

162970 SHEET 03 OF 09

STEP 8 - INSTALL HEAD/SILL AND INTERMEDIATE HORIZONTALS


TUBULAR HORIZONTALS

128405 SCREWS
#12 X 7/8"
FLAT HEAD
TYPE AB



THERMAL BREAK
TO BE 1/4"
SHORT AT EACH
END OF
HORIZONTALS

1/4"




STEP 8 - INSTALL HEAD/SILL AND INTERMEDIATE HORIZONTALS

REFERENCE INSTRUCTIONS 162983 FOR
EXTERIOR FRAME PERIMETERS


OPEN BACK HORIZONTALS AND LAST BAY HORIZONTALS.

FILLER AVAILABLE WHEN OPEN BACK IS EXPOSED AND AT
EYE LEVEL.


128405 SCREWS
#12 X 7/8"
FLAT HEAD TYPE AB



INSTALLING CEILING INTERMEDIATE
OPEN BACK HORIZONTAL




INSTALLING STOOL INTERMEDIATE
OPEN BACK HORIZONTAL



STEP 9 - INSTALL JOINT PLUGS

ALL SURFACES AND GROOVES MUST BE
CLEANED PER THE SEALANT MANUFACTURER'S
RECOMMENDATIONS.

JUST BEFORE INSTALLING JOINT PLUGS
APPLY SEALANT AS SHOWN FILLING
GASKET POCKET AND ADAPTER GROOVE.




FILL
ADAPTER
GROOVE


FILL
GASKET
POCKET

FACE VIEW


162970 SHEET 04 OF 09




JOINT PLUG
162321 (1" FRAMING)
162322 (1/4" FRAME MEMBERS)




APPLY SEALANT TO THIS
FACE OF JOINT PLUG



SEAL AROUND JOINT PLUG
EDGES AND COMPLETELY
OVER JOINT PLUG WITH
SEALANT AND TOOL
AS SHOWN



SEAL AROUND JOINT PLUG
EDGES AND COMPLETELY
OVER JOINT PLUG WITH
SEALANT AND TOOL
AS SHOWN



REFERENCE INSTRUCTIONS 162983 FOR
EXTERIOR FRAME PERIMETERS

KAWNEER
AN ARCONIC COMPANY


Product Engineering & Development

95449-115
04/21/17



1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS

162970 SHEET 04 OF 09

STEP 10 - INSTALL PERIMETER FILLERS AND SPANDREL ADAPTERS WHERE APPLICABLE





STEP 11 - SEAL INTERIOR OF VERTICAL SPLICE JOINTS



STEP 11 - SEAL INTERIOR OF VERTICAL SPLICE JOINTS

ALL SURFACES AND GROOVES MUST BE
CLEANED PER THE SEALANT MANUFACTURER'S
RECOMMENDATIONS.



Product Engineering & Development

95449-115
04/21/17

1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS

162970 SHEET 05 OF 09

STEP 12 - INSTALL INTERIOR GLAZING GASKETS

GASKETS SHOULD BE INSTALLED JUST PRIOR TO GLASS TO AVOID CONTAMINATION BY JOB SITE DEBRIS. GASKET GROOVES AND POCKETS SHOULD BE CLEAN.


IN TEMPERATURES COLDER THAN 50° F ARRANGEMENTS SHOULD BE MADE TO WARM GASKETS BEFORE INSTALLATION. THIS WILL PREVENT EXCESSIVE GLAZING PRESSURE ON THE GLASS DUE TO COLD, STIFF RUBBER GASKETS.

GASKETS CAN BECOME DEFORMED DURING STORAGE IN CARTONS. THEY SHOULD BE REMOVED FROM CARTONS SEVERAL HOURS PRIOR TO GLAZING AND LAID FLAT OR HUNG TO ALLOW RECOVERY OF CORRECT SHAPE. TEMPERATURES SHOULD BE AT LEAST 50° F TO ALLOW THIS.


GASKET INSTALLED LENGTH TO BE DAYLITE OPENING. GASKETS TO BE CUT LONG FOR SOME "CROWD-IN". GASKETS SHOULD NEVER BE "STRETCHED TO FIT".

"CROWD-IN" TO BE 1/8" PER FOOT UP TO 5'-0", 3/16" PER FOOT UP TO 8'-0", 1/4" PER FOOT OVER 8'-0".

JUST BEFORE INSTALLING VERTICAL AND HORIZONTAL GASKETS FACE SEAL JOINTS AT ALL (4) CORNERS. ALSO SEAL SCREW HEAD AT TOP HALF OF HORIZONTAL




TYPICAL




GASKET 027850

PERIMETER WHERE APPLICABLE




GASKET 027857

STEP 12 - INSTALL INTERIOR GLAZING GASKETS




STEP 13 - INSTALL SETTING BLOCKS



STEP 14 - INSTALL EXTERIOR GASKETS INTO PRESSURE PLATES


REFERENCE GASKET NOTES IN STEP 12
SAME NOTES APPLY.

REFERENCE INSTRUCTIONS 162983 FOR
EXTERIOR FRAME PERIMETERS




GASKET 027850

VERTICAL GASKETS ARE TO RUN CONTINUOUS EXCEPT AT HEAD AND SILL CONDITIONS THE GASKET IS TO BE CUT 1" SHORT THIS IS FOR THE SEAL AT SECTION D-D STEP 17 - SHEET # 8




PERIMETER PRESSURE PLATE



HORIZONTAL GASKET TO BE SAME LENGTH AS PRESSURE PLATE

PERIMETER WHERE APPLICABLE



GASKET 027857 AT ONE SIDE. DO NOT CUT 1" SHORT.




1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS



Product Engineering & Development

95449-115
04/21/17


STEP 15 - INSTALL GLASS



MAXIMUM TEMPORARY SPACING IS 30". IF WINDS GREATER THAN 50 MPH (80KPH) ARE EXPECTED, ADDITIONAL TEMPORARIES MAY BE REQUIRED. CONSULT YOUR SEALANT AND/OR INFILL SUPPLIER FOR SPACING RECOMMENDATIONS. INSTALL PRESSURE PLATES WHERE POSSIBLE.



STEP 16 - INSTALL GLASS SIDE BLOCKS



INSTALL SIDE BLOCKS, COMPRESSING AS SHOWN


STEP 17 - INSTALL EXTERIOR PRESSURE PLATES



RECOMMEND USING TORQUE LIMIT TOOL 162399 SEE NOTE.

HOW TO SET TORQUE LIMIT

- 1) ATTACH ANY CALIBRATED TORQUE INDICATOR TO OUTPUT STUB (1) AND DETERMINE PRESENT TORQUE SETTING WHILE HOLDING THE BODY (5), OR VICE-VERSA.
- 2) REMOVE SNAP RING (2) AND LOCKING PLATE (3).
- 3) ADJUST NUT (4) WITH OPEN-END WRENCH : CLOCKWISE TO INCREASE TORQUE, COUNTER- CLOCKWISE TO DECREASE TORQUE.
- 4) OBTAIN NEW TORQUE READING WITH THE CALIBRATED TORQUE INDICATOR. REPEAT PRECEDING STEP IF MORE ADJUSTMENT IS NECESSARY TO REACH DESIRED LIMIT.
- 5) REPLACE LOCKING PLATE INTO NOTCHES AND INSTALL SNAP RING. IF LOCKING PLATE DOES NOT "SEAT", MOVE THE ADJUSTING NUT SLIGHTLY UNTIL IT DROPS IN PLACE. THE DIRECTION IS BEST DETERMINED BY WHETHER A MINIMUM TORQUE APPLICATION OR A MAXIMUM ONE IS DESIRED.




INSTALL PRESSURE PLATES USING SCREWS 128406 1/4-14 X 1" HEX WASHER HEAD TYPE AB.

SCREWS ARE TO BE LOCATED 9" ON CENTER. ALWAYS LOCATE A SCREW AS CLOSE AS POSSIBLE TO A HORIZONTAL JOINT. THIS WILL PROVIDE MAXIMUM PRESSURE FOR THE CRITICAL JOINT SEALS.


INSTALL HORIZONTAL PRESSURE PLATES WITH WEEP HOLES TOWARDS TOP OF HORIZONTAL.

AT EACH HORIZONTAL AND VERTICAL PRESSURE PLATE INSTALL TWO SCREWS PART WAY, THEN INSTALL THE THIRD SCREW ALL THE WAY, AND THEN TIGHTEN THE FIRST TWO SCREWS. THIS ELIMINATES LATERAL WALKING OF THE PRESSURE PLATE POSITION.

TORQUE ALL SCREWS TO 95 TO 100 INCH POUNDS. DURING COLD WEATHER, TORQUE SCREWS TO 50 INCH POUNDS UNTIL ALL 4 SIDES HAVE BEEN CLAMPED. THEN TORQUE SCREWS TO 95 TO 100 INCH POUNDS.



CLEAN JOINT PER SEALANT MANUFACTURER'S RECOMMENDATIONS



Product Engineering & Development

95449-115
04/21/17


1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS

**STEP 17 - INSTALL EXTERIOR
PRESSURE PLATES**

INSTALL VERTICAL PRESSURE PLATES

NOTE - THE TORQUE LIMIT TOOL WAS DESIGNED TO BE USED WITH A HAND DRIVEN DEVICE. THE TOOL CAN BE ADAPTED TO A DRILL MOTOR IF USED AT A MAXIMUM SPEED OF APPROXAMITLY 300 RPM. HIGHER SPEEDS CAN CAUSE OVERHEATING AND AFFECT THE ACCURACY. AFTER APPROXAMITLY 1 HOUR OF TOOL USAGE CHECK TORQUE SETTINGS WITH A TORQUE WRENCH.


INTERMEDIATE HORIZONTAL
VISION OVER SPANDREL



TOOL EXCESS
SEALANT

HEAD CONDITION
SILL SAME

VERTICAL GASKET
STOPS 1" SHORT
AT HEAD AND SILL
CONDITIONS




TOOL EXCESS
SEALANT

PERIMETER FILLER

HEAD CONDITION
SILL SAME

VERTICAL GASKET
STOPS 1" SHORT
AT HEAD AND SILL
CONDITIONS




TOOL EXCESS
SEALANT

INSTALL VERTICAL PRESSURE PLATES


VERTICAL EXPANSION JOINTS

TOP OF VERTICAL
MULLION TO TOP
OF PRESSURE
PLATE IS 1-1/2"



AT TOP PRESSURE PLATE
LOCATE SCREW CLOSE TO
THE MULLION JOINT BUT
NOT BELOW THE JOINT


CLEAN JOINT
PER SEALANT
MANUFACTURER'S
RECOMMENDATIONS



COMPLETELY SEAL JOINT.
DO NOT LET SEALANT
INTERFERE WITH COVER
SNAP. OVERLAP PRESSURE
PLATE FACE CREATING
A BAND-AID SEAL.


INSTALL HORIZONTAL PRESSURE PLATES

CENTER HORIZONTAL PRESSURE PLATES
SO END GAPS ARE EQUAL.




INTERMEDIATE
HORIZONTAL
VISION OVER
SPANDREL

SEAL JOINTS AS
SHOWN. TOOL
SEALANT. THIS
SEAL IS TO JOIN
AND ADHERE TO
THE JOINT PLUG
SEALS



CLEAN JOINT PER
SEALANT
MANUFACTURER'S
RECOMMENDATIONS

DO NOT LET THE SEAL INTERFERE
WITH THE COVER SNAP



GASKET
027850


B-B

GASKET
027850

FACE VIEW

PERIMETER FILLER

HEAD HORIZONTAL
SILL SAME




SEAL JOINTS AS
SHOWN. TOOL SEALANT.
THIS SEAL IS TO JOIN
AND ADHERE TO THE
JOINT PLUG SEALS.


REFERENCE INSTRUCTIONS 162983
FOR EXTERIOR FRAME PERIMETERS

SEAL BETWEEN PRESSURE
PLATE AND HEAD/SILL END
CAP AS SHOWN.

HEAD HORIZONTAL
SILL SAME




SEAL JOINTS AS
SHOWN. TOOL
SEALANT. THIS
SEAL IS TO JOIN
AND ADHERE TO
THE JOINT PLUG
SEALS.



CLEAN JOINT
PER SEALANT
MANUFACTURER'S
RECOMMENDATIONS

DO NOT LET THE SEAL INTERFERE
WITH THE COVER SNAP

VERTICAL GASKET
STOPS 1"
SHORT OF END



GASKET
027857


E-E

GASKET
027850

GASKET
027850

FACE VIEW

DO NOT LET THE SEAL INTERFERE
WITH THE COVER SNAP



C-C
GASKET
027850

KAWNEER
AN ARCONIC COMPANY




Product Engineering & Development

95449-115
04/21/17

1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS



STEP 18 - INSTALL PERIMETER WEATHER SEALS

PERIMETER WEATHER SEALS ARE INSTALLED AT THE PRESSURE PLATE LOCATION AS DETAILED BELOW. (THIS SEAL SHOULD BE INSTALLED BEFORE COVERS ARE APPLIED WHEN COVERS DEEPER THAN 3/4" ARE USED) EXTERIOR COSMETIC SEALS AT THE COVER MAY BE APPLIED AT THE HEAD, JAMB AND SILL. COSMETIC SEAL AT SILL COVERS MUST ALL WATER DRAINAGE TO THE EXTERIOR.




STEP 19 - INSTALL EXTERIOR COVERS

CARE MUST BE TAKEN TO AVOID DAMAGE TO COVERS DURING INSTALLATION. USE A 18" LONG PIECE OF 2" X 4" WOOD ALONG WITH A HAMMER OR MALLET TO SEAT THE COVER.





STEP 19 - INSTALL EXTERIOR COVERS

PINNING OF ALL VERTICAL COVERS IS REQUIRED FOR BOTH SIDES. DRILL A 0.106 DIA. HOLE (#36 DRILL) AND INSTALL 128920 SCREWS #6 X 3/8" PAN HEAD TYPE B. LOCATE PINNING AT A HORIZONTAL CLOSEST TO THE COVER HEIGHT CENTER.




NOTE FOR 5" SIGHTLINE COVERS
DUE TO LARGE EXTRUSION TOLERANCES, 5" SIGHTLINE COVERS MAY REQUIRE SEALANT OR PINNING TO HOLD IN PLACE.

INSTALL HORIZONTAL COVERS WITH THE WEEP HOLES DOWN



REMOVING COVERS

COVERS CAN BE SAVED IF TOLERANCES ARE NOT TOO TIGHT AND THE COVER IS REMOVED WITH EXTREME CARE



Product Engineering & Development

95449-115
04/21/17

1600 WALL SYSTEM™ 1
CURTAIN WALL
INSTALLATION
INSTRUCTIONS